

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>6E</u>	<u>D-5</u>
	T <u>29N</u> R <u>6E</u>	<u>D-7</u>
	T <u>29N</u> R <u>6E</u>	<u>C-7</u>
	T <u>29N</u> R <u>6E</u>	<u>F-5</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl R. Johnson, in a field survey on June 6, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-5 - Set midway and on line between found section corners.
- D-7 - Left found 2" pipe in place.
- C-7 - Found 1/2" bar w/cap in place by Scott Engr.
- F-5 - Set midway and on line between found section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---------------------------|---------------------------|--------------------------------|
| D-5 - <u>N 1/4</u> Corner | D-7 - <u>S 1/4</u> Corner | C-7 - <u>SW</u> Corner |
| D.N.R. Monument | 2" pipe | 5/8" bar w/cap <u>RS</u> 22435 |
| 5" Cedar N39°E 13.4' | 6" Cedar N34°E 9.9' | 5" Maple N71°E 17.3' |
| 8" Cedar S58°E 7.7' | 6" W. Pine S71°E 20.4' | 5" Red Oak S54°W 40.3' |
| 4" Cedar S44°W 11.6' | 10" W. Pine S85°W 23.9' | 5" Red Oak N32°W 12.3' |
| 6" Cedar N17°W 14.5' | | |
| | F-5 - <u>N 1/4</u> Corner | |
| | D.N.R. Monument | |
| | 14" W. Birch N8°W 63.2' | |
| | 8" Maple S40°W 58.3' | |

Signed by Carl R. Johnson
 Surveyor's Michigan License No. 30083

Date 8/7/89

