

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Alpena</u> <small>(County)</small>	Located In:	Corner Code $\neq$
1. Public Land Survey	T <u>29N</u> R <u>6E</u>	D-6
	T <u>29N</u> R <u>6E</u>	E-6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>17</u> T <u>29N</u> R <u>6E</u>	13
	S <u>17</u> T <u>29N</u> R <u>6E</u>	9
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl R. Johnson in a field survey on June 7, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 D-6 - Set at computed true intersection of  $\frac{1}{4}$  lines  
 13 - Set by standard survey procedure for subdivision of a section.  
 9 - Set by standard survey procedure for subdivision of a section.  
 E-6 - Set midway and on line between found section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                         |                              |  |
|-------------------------|------------------------------|--|
| D-6 - Center of Section | 13 - Center SW $\frac{1}{4}$ | 9 - E $\frac{1}{8}$ , E-W $\frac{1}{4}$ Line |
| D.N.R. Monument         | 5/8" bar w/cap               | 5/8" bar w/cap                               |
| 14" Ash N32°E 17.0'     | 6" Cedar N25°W 8.2'          | 8" Spruce S33°E 25.3'                        |
| 10" Ash S51°W 37.5'     | 12" Cedar S41°E 27.5'        | 14" Balsam S58°W 27.6'                       |
|                         | 5" Spruce S72°W 8.7'         |  |

- E-6 - East  $\frac{1}{4}$  corner  
 D.N.R. Monument  
 6" Cedar N17°W 13.8'  
 10" Cedar S37°E 13.9'  
 4" Cedar S56°W 9.3'

Signed by Carl R. Johnson Date 8/7/89  
 Surveyor's Michigan License No. 30083

