

SURVEY & MONUMENT

1995 Alpena County Remonumentation Corner

LIBER 1 PAGE 373

RECORDED ALPENA COUNTY MI

JUL 31 9 59 AM '95

AUG 2 1995 For corners in

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS

Table with columns: Alpena (County), Located In, Corner Code. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is marked at row 9, column A.

I, Daniel T. Kibbe, in a field survey on May 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1839: G.L.O. Survey by Thomas Pattison - set post corner & referenced: Hemlock 14 - S 48 W - 58 Hd. Maple 11 - N 35 W - 45. 1908: County Survey by Jos. W. McNeil - found corner plain, set large W. Pine stake for corner. 1914, 27: County Survey by Jos. W. McNeil - found corner previously set. 1932: County Survey by Wm. H. LeRoy - replaced stake with 6"x6"x36" concrete & referenced. 1959: Monument Witness Record by N.C.C. Survey Chief - found 1/2" bar in 6"x6" conc. mon. & ref. MSHD Highway Plans 1962: Monument Witness Record by Gerald Wozniak - 1 1/4" pipe in mon. box & referenced. MSHD - Updated witnesses. 1973,82: Surveys by James Scott and Duane MacNeill - found mon. box. B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993: LCRC & Monument Witness Record by Clifford Lindgren, MDOT - found 1 1/4" pipe in mon. box & referenced.

1995: Found 1 1/4" pipe in monument box, 6.3' West of M-65 C/L.

This corner position is compatible with county and local surveys and agrees with MDOT records. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY PEER APPROVED 6/6/95 [Signature]

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 1995: Placed 3" aluminum cap stamped to identify the corner on 1/2" iron rod over existing 1 1/4" pipe in monument box. Referenced: N 57° W - 127.80' - N/Tag in 18" Ash N 88° W - 78.95' - NE cor. I-beam gate post S 53° W - 101.91' - N/Tag in wood post N 64° E - 55.47' - S. edge of S. let of stop sign.



Signed by [Signature] Date July 24, 1995 Surveyor's Michigan License No. 37278