

**1999 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 21 2000

SECTION

For corners in

Alpena Located In: Corner Code #
(County)

1. Public Land Survey T 29N R6E B-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____



L- 2 P- 277
12/10/1999 01:39P
Page: 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on June 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- Not a GLO corner
- 1899: County Survey by Wm. H. LeRoy: Set 1/4 section for North side of Section 6, 70 links East of B-13 T30N R6E.
- 1908: County Survey by Jos. W. McNeil: Ran to corner set by Wm. H. LeRoy 65 Links East of B-13 T30N R6E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Remon. Survey by Daniel T. Kibbe-Found no corner evidence, propose to set B-1 on line from B-13 to C-13 65 links (42.90') East of B-13 per Jos. McNeil's 1908 survey.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.
- Referenced:
 Clump oak N30W 70.41'
 30" Oak-set tag-S10W 74.65'
 Guy Pole-set tag-S69W 70.40'
 13" Locust S43E 64.77'
 B-13 West 42.90'

P.A. 345 ALPENA COUNTY
 PEER APPROVED 9/16/99
D.P.R. Cur

Signed by _____
 Surveyor's Michigan License No. 37278

Date November 30, 1999

