

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

JUL 31 9 59 AM '95

REGISTER OF DEEDS

For corners in

Table with columns: Alpena (County), Located In:, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (8,20) contains a small circle.

I, Daniel T. Kibbe, in a field survey on June 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 1839: G.L.O. Survey by Thomas Pattison - set quarter section post & referenced: Beech 12 - S 24 W - 24 / Ironwood 8 - N 45 E - 48.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1995: Found no corner. Only evidence found is an old four-way fence corner. Due to the straightness and location of the fences, it is accepted that the true position of the corner is best represented by the four-way fence corner.

SURVEY & REMONUMENTATION

AUG 28 1995

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 6/29/95 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set 18"x 1/2" iron rod with 3" aluminum cap stamped to identify the corner. Referenced: N 65° E - 45.40' - Set N/Tag in 21" Red Oak; N 25° E - 30.58' - Set N/Tag in 7" Ironwood; S 07° W - 30.72' - Set N/Tag in 13" Maple; S 53° W - 62.60' - Set N/Tag in 13" Red Oak



Signed by [Signature]

Date July 24, 1995

Surveyor's Michigan License No. 37278