

SURVEY & REMONUMENTATION

FEB 03 1998

1997 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
 For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29</u> N R <u>6E</u>	<u>M-7</u>
	T <u>29</u> N R <u>7E</u>	<u>A-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Liber **00002** Page **0121**

STATE OF MICHIGAN
 County of Alpena
 Recorded
 11-06-1997 15:32:00
 Kathy J. Matash
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on March 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 ALPENA COUNTY
 PEER APPROVED 7/23/97
Daniel T. Kibbe

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO survey by Lewis Clason - set post, referenced: Y. Birch 20-S57W-59 / Cedar 14-N12W-24
- 1911: County survey by Jos. W. McNeil - set large cedar stake, referenced: O.B.T. standing Y. Birch 20-S57W-59 remains of other two O.B.T.'s, N.B.T.'s: Cedar Stump 14-S57W-42 / Willow 6-S26E-34
- 1979: Survey by Duane R. MacNeill - set 1" pipe, referenced: N45W - 48.81' Power Pole / S45W - 44.22' Fence corner / S45E - 44.12' Fence corner
- 1993: Survey by David Guthrie - existing 1" pipe (DRM)
- 1996: County Road Commission Survey - found pipe w/cap, referenced: N43E - 49.30' Fence Corner / N38W - 47.08' Power Pole / N58W - 80.12' 3" Spruce

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Survey by Wayne Lewis - Found pipe and cap, referenced: N60W - 80.25' 4" Balsam / N45W - 47.30' P. Pole / N45E - 49.40' Fence Post / S60E - 94.60' 8" Elm
- B. 1997: Found 1" pipe and cap 2' South of E-W centerline road, in centerline road to North, 2' West of centerline road to South.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod
 Referenced:
 N55W - 80.15' - Found tag in 4" Balsam
 N34W - 47.15' - Found tag in P. Pole
 S63E - 94.45' - Found tag in 8" Elm
 N46E - 49.44' - Found tag in Fence Post
 S41E - 45.38' - Found old tag in corner fence post bent SE



Signed by *Daniel T. Kibbe*
 Surveyor's Michigan License No. 37278

Date October 24, 1997