

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>6E</u>	<u>G-4</u>
	T _____ R _____	
2. Property Controlling in Section	S <u>10</u> T <u>29N</u> R <u>6E</u>	<u>14</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on July 01, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9	●	10		11		12	
5								●				
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4	GLO set section post – Lewis Clason D.S. 1839. Wit: Hemlock 7" N 56° W 6 links Black Ash 9" S 28° E 39 links	14 - This corner was not established during the original government survey.
-----	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4	Found and accepted a 1/2" iron rod for the West Quarter Corner of Section 10. This position fits well with a 1904 survey done by Jos. McNeil, County Surveyor.	14 - Established the Southeast Corner of the Northeast Quarter of the Southeast Quarter of Section 10 per standard BLM instructions for the subdivision of a section.
-----	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4	Found a 1/2" iron rod. Wit: Set nail in 6" Spruce N 29° E 50.12' Set nail in 10" Spruce N 44° W 47.50' Set nail in 4" Ash N 74° W 94.91' Power pole S 60° E 112.57'	14 - Set 5/8" x 32" rerod with cap and set carsonite marker post. Wit: Set nail in 7" Ash S 87° E 14.28' Set nail in 10" Cedar S 68° W 32.20' Set nail in 3" Ash N 46° W 12.03' Set nail in 3" Ash N 19° E 23.73'
-----	---	---

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981



Date 6-14-99