

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>6E</u>	<u>K-2</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on July 15, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2	●	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2 GLO set section post.
 Witness: Cedar 8" S 58° E 29 links
 Cedar 10" N 18° W 16 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Reestablish the West Quarter Corner of Section 1 per Thomas Fabis, PS #31591, 05/02/95 remonumentation work in the area. This position fits well with occupation and a 1904 survey in Section 1 by Joseph McNeil, County Surveyor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Set 5/8" x 32" reroed with cap and set carsonite marker post.
 Witness: Set nail in 3" Cherry East 25.99'
 Set nail in 6" Cherry S 12° E 89.42'
 Set nail in 6" twin Apple N 09° E 109.67'
 Centerline north-south
 gravel road East 1' ±
 Carsonite marker post set
 In east-west fence line East 28'



Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 6-14-99