

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>6E</u>	<u>I-1</u>
	T <u>29N</u> R <u>6E</u>	<u>J-3</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on July 02, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	GLO set section post – Lewis Clason 1839.	J-3	GLO set section post.
Wit:	Beech 7" S 28° E 17 links	Wit:	Cedar 7" S 66° W 27 links
	Hard Maple 9" S 54° W 33 links		Hemlock 10" N 59° E 11 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1	Found and accepted a 1 3/4" iron pipe as used by local surveyors for surveys in the area. This position fits well with distances recorded in a Certificate of Survey, by James L. Scott, RLS #8318, and filed in Liber 1, Page 139 of Alpena County Register of Deeds.	J-3	Found and accepted a boat spike set over an existing iron as witnessed by Thomas Fabis, PS #31591.
-----	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----	----------------------------------------------------------------------------------------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1	Found 1 3/4" iron pipe. Set 5/8" x 32" rerod with cap inside iron pipe.	J-3	Found boat spike set by T. Fabis, PS #31591, in centerline of east-west gravel road.
Wit:	Power pole S 61° W 61.40'	Wit:	* Nail set in 6" Apple S 50° W 44.41'
	Power pole S 40° E 47.11'		* Nail set in 6" Elm S 25° E 23.39'
	Set nail in 3" Balsam N 72° E 33.38'		Set nail in 3" Apple S 65° E 61.85'
	Set nail in 5" Aspen N 42° E 41.29'		* Fence post N 6° E 46.63'
	2" iron pipe West 15.29'		Carsonite marker post in east-west fence line South 31' ±



(old Fabis witness)

Signed by Carl T Kiiskila

Date 6-14-99

Surveyor's Michigan License No. 33981