

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 29N R 6E	K-5
	T 29N R 6E	K-4
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on June 30, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11	●	12	
5											●		
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5	GLO - Hard Maple 5" for post - Lewis Clawson D.S. 1839. (No witnesses recorded.)	K-4	GLO set post - Lewis Clawson 1839. Wit: Cedar 18" S 55° E 7 links Cedar 18" N 47° W 14 links
-----	---	-----	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5	Found and accepted a 1/2" rerod as witnessed by Earl T. Lewis, PS #27452, per his Certificate of Survey recorded in Liber 2, Page 452 of Alpena County Register of Deeds.	K-4	Reestablished the East Quarter Corner of Section 11 at the intersection of an old east-west fence line and an old fence line south. Distances north and south fit reasonably well with GLO distances.
-----	---	-----	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5	Found 1/2" rerod. Wit: Set nail in 14" Ash N 20° E 35.98' Set nail in 28" Oak N 60° E 49.39' Set PK nail in utility pole S 12° E 34.05' Set nail in 26" Oak N 42° W 54.57' Fence post S 8° W 32.64' A barbed wire fence runs north and south from this corner.	K-4	Set a 1" pipe with PS cap. Wit: Set nail in 6" Ash S 16° W 18.68' Set nail in 7" Cedar S 27° E 30.35' Set nail in 5" Ash N 30° W 6.14' Set nail in 4" Balsam N 75° W 25.21'
-----	--	-----	---

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981



Date 6-14-99