

SURVEY & REMONUMENTATION

FEB 03 1998 1997 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

Liber **00002** Page **0122**

STATE OF MICHIGAN
 County of Alpena
 Recorded
 11-06-1997 15:32:09
 Kathy J. Matash
 REGISTER OF DEEDS

Alpena (County)	Located In:	Corner Code #
1. Public Land Survey	T29N R7E	B-7
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on March 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 ALPENA COUNTY
 PEER APPROVED 7/23/97
Out. P. Curran

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7		●											
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO survey by Lewis Clason - Set 1/4 post, referenced: Beech 14-N27E-29 / Beech 26-S56W-30
- 1897: County Survey by Wm. H Lindey - reestablished old 1/4 S Cedar Stake
- 1911: County Survey by Jos. W. McNeil - set new stake
- 1978: County Rd. Commission Survey by Gary St. Charles - fd. 1/2" rerod
- 1993: Survey by David Guthrie - existing 1/2" rerod
- 1997: Survey by Wayne Lewis - single proportion from C.S. notes, referenced: North-38.30' - P. Pol S30W - 38.65' - 5" Ash / S70E-72.00' - 5" Ash / S75E-101.20' - 12" Elm.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Reset 1/4 corner B-7 in approximate centerline of E-W road and on fence line North from 1993 R.S. Scott survey in SW 1/4 of Section 18. This corner position fits 1978 Alpena County Road Commission survey. This corner is 6.0' North 0.5' East of a found Wayne Lewis bar and cap which was set by single proportionate method.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.
 Referenced:
 N59E - 51.08' - fd. old tag in old fence post leaning to the east
 N09E - 32.20' - fd. tag in power pole
 S47W - 43.41' - fd. tag in 5" Ash
 S55E - 73.88' - fd. tag in 6" Ash
 South 6.06' found bar and cap #41922



Signed by *Daniel T. Kibbe*
 Surveyor's Michigan License No. 37278

Date October 24, 1997