

**SURVEY & REMONUMENTATION**

FEB 03 1998

1997 Alpena County Remonumentation Corner  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corner SECTION

Alpena  
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>29</u> N R <u>7E</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber **00002** Page **0112**

STATE OF MICHIGAN  
 County of Alpena  
 Recorded  
 11-06-1997 15:30:25  
 Kathy J. Matash  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Daniel T. Kibbe, in a field survey on March 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 ALPENA COUNTY  
 PEER APPROVED 7/23/97  
*D. B. [Signature]*

- A. Description of original monument and accessories and/or subsequent restoration:
- 1839: GLO survey by Lewis Clason - set post, referenced: Hem 22-S47E-22 / Hem 10-N19W-06
  - 1886 & 1896 - County survey by Fred A. Rice - set new stake in place of old one, referenced: Pine Stubb 28-S18½E-13 links / Pine Stubb 30-N26W-52 links
  - 1905 & 1911 - County Survey by Jos. W. McNeil - dug up old stake as set new one
  - 1978: County Rd. Comm. survey by Gary St. Charles - fd. 3/4" pipe, referenced: N40E-52.40' - Power Pole / S70W - 121.20' - Light Pole
  - 1986: Survey by David Guthrie - iron stake in mon box
  - 1996: County Rd. Comm. survey by Gary St. Charles - fd. 1/2" rerod in mon box, referenced: N28W-50.63' - Fence Corner / N40E-52.40' - Power Pole / S30W - 141.00' - 4" Fruit Tree / S70W - 121.20' - Light Pole
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1997: Found ½" rebar in monument box in centerline intersection.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1997: Placed 3" Alpena County cap stamped to identify the corner over ½" iron rod in monument box.
- Referenced:
- S52W - 50.97' - Found tag in Light Pole
  - N50E - 50.41' - Found tag in Power Pole
  - N40W - 51.04' - Found tag in fence post
  - S60W - 101.56' - N.W. corner of block on porch



Signed by *Daniel T. Kibbe*  
 Surveyor's Michigan License No. 37278

Date October 24, 1997