

FEB 03 1998

SECTION

1997 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey

T29N R7E

C-12

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Liber 00002 Page 0117

STATE OF MICHIGAN
County of Alpena
Recorded
11-06-1997 15:31:23
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on March 27 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 ALPENA COUNTY
PEER APPROVED 7/23/97
D. T. Kibbe

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO survey by Lewis Clason - set 1/4 Section post, referenced: Tam 7-S54E-13 / Cedar 7-N48W-34
- 1912: County Survey by Jos. W. McNeil - corner plain, set new cedar stake in place of old one, referenced: (new) Tam 13-West-32
- 1978: Survey by David Guthrie - fd two rebar 16.3' apart

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found 1/2" rebar. This corner position fits found rebars at 1/8 corners to the North and South, both 1/8 corner are compatible with occupation.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.
Referenced:
S35E - 47.91' - set tag in fd. blaze - 5" Balsam
S70E - 44.63' - set tag in fd. blaze - 6" Cedar
S60W - 47.40' - set tag in fd. blaze - 8" Ash
S03W - 16.1' - Found rebar
S11W - 5.2' - Found pipe



Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278

Date October 24, 1997