

1995 ALPENA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 16 2 53 PM '95

Wm. J. Johnston
REGISTER OF DEEDS

or corners in

Alpena (County) Located In: Corner Code #

Public Land Survey T 29N R 7E E-3 (NW, 9)
T R Ossineke Twp.
T R
T R
T R

Property Controlling S T R
in Section S T R

Miscellaneous S T R
Property in Sec. S T R

Lot No. , Recorded Plat
Private Claims

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Thomas L. Fabis, in a field survey on March 23, 1995, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - 1839: G.L.O. Survey by Lewis Clason - Set post & referenced: (Tam 10 - N22W - 12, Cedar 9 - S10E - 14).
 - 1905: County Survey by Jos. W. McNeil - Set stake in place of old one in center of road bed.
 - 1975-76: Road Commission Surveys by Gary St. Charles - Found 1/2" iron & Referenced.
 - 1988: Recorded Survey by Earl T. Lewis - Found 1/2" rod & referenced.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - 1995: Found 1/2" iron rod and the following witnesses matching the 1975-76 Road Commission Surveys and the 1988 Recorded Survey by Earl T. Lewis: (Power Pole - S45W - 43.98' and Anchor Pole - N35W - 45.10').

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

SURVEY & REMONUMENTATION

AUG 23 1995


- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Set 3" dia. aluminum cap, stamped to identify the corner, over existing 1/2" iron rod.

- Reestablished witnesses are:
- Power Pole - S45W - 43.98'
 - Anchor Pole - N35W - 45.10'
 - Set tag #31591 in 6" Cedar - S44W - 51.12'
 - Set tag #31591 in 2" Spruce - S32W - 65.60'

P.A. 345 ALPENA COUNTY
PEER APPROVED *May 18 1991*
D. B. L...

Signed by *Thomas L. Fabis*



Date *June 12, 1995*

Surveyor's Michigan License No. 31591