

SURVEY & REMONUMENTATION COMMISSION APR 06 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DEC 12 9 30 AM '94

REGISTER OF DEEDS

Alpena (County) Located In: Corner Code # Public Land Survey T 29 N 7 E G-2

Register of Deeds Stamp & File Number

Lot No. Recorded Plat Private Claims

Earl T. Lewis in a field survey on July 22 19 94

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column G and row 3.

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

(GLO) August 18, 1839, Lewis Glason set post, witnesses given: Aspen 16, N 47 E, 15 / Do 15, S 27 W, 16. 1904, Joseph W. McNeil, no monumentation or witnesses given. 1911, Joseph W. McNeil, no monumentation or witnesses given. 1912, Joseph W. McNeil, no monumentation or witnesses given. 1976, Alpena County Road Commission found 4" concrete monument, set 1/2" rebar over top in monument box, witnesses given: NW 38.50' Fence Post / East 31.56' Fence Post

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994, found 1/2" rebar in monument box.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" rebar in monument box, witnessed: N 15° E 241.78' Power Pole S 35° E 107.14' Telephone Riser S 20° E 173.05' Power Pole S 15° E 227.60' Telephone Riser No other witnesses available

P.A. 345 ALPENA COUNTY PEER APPROVED 9/29/94

Signed by Earl T. Lewis Date December 5, 1994

Surveyor's Michigan License No. 27452