

1994 ALPENA COUNTY REMONUMENTATION CORNER LIBER 1 PART 331
 SURVEY & REMONUMENTATION
 APR 06 1995
 COMMISSION

RECORDED
 ALPENA COUNTY MI.

LAND CORNER RECORDATION CERTIFICATE 007218
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 12 9 31 AM '94

Springer A. Johnston
 REGISTER OF DEEDS

for corners in
Alpena
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>29</u> N	<u>7</u> E	<u>G-4</u>
	T	_____	_____	_____
	T	_____	_____	_____
	T	_____	_____	_____
2. Property Controlling in Section	S	_____	_____	_____
	S	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	_____	_____
	S	_____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl T. Lewis in a field survey on July 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 (GLO) August 18, 1839, Lewis Glason set post, witnesses given: W. Pine 20, S 36 E, 23 / Elm 14, N 40 W, 221.
 1904, Joseph W. McNeil, found large cedar stake at south edge of culvert.
 1910, Joseph W. McNeil, no monumentation or witnesses given.
 1973, James L Scott P.S., no monumentation or witnesses given.
 October 29, 1976, Alpena County Road Commission found 6" concrete monument, set 1/2" iron in monument box, witnesses given: N 88° W 52.43' Tel Pole / S 52° 45' E 56.55' Power Pole
 1978, David B. Guthrie P.S., found monument box, witnesses given: West, Power Pole, 51.88 feet / S 80° E, Power Pole, 56.41 feet.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994, found 1/2" rebar in monument box.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1994, Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" rebar in monument box, witnessed:
 West 52.1' Tel. Pole
 S 45° E 56.65' P. Pole
 N 75° E 56.75' Stop Sign
 N 80° W 80.4' GTE Marker
 N 45° W 173.04' Light Pole

P.A. 345 ALPENA COUNTY
 PEER APPROVED 9/29/94
Neil B. Galt

December 6, 1994

Signed by Earl T. Lewis Date _____
 Surveyor's Michigan License No. 27452