

SURVEY &
 REMONUMENTATION
 1994995
 APR 08 1995
 COMMISSION

007144

RECORDED
ALPENA COUNTY MI.

Dec 8 10 11 AM '94
Monique A. Johnston
 REGISTER OF DEEDS

Alpena County Remonumentation corner

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Alpena _____ Located In: _____ Corner Code: ##
(County)

1. Public Land Survey	T 29N R 7E	G-10 (W $\frac{1}{2}$, 27)
	T _____ R _____	Ossineke Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas L. Fabis, in a field survey on May 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

- 1839: G.L.O. Survey by Lewis Clason - Set $\frac{1}{2}$ post and referenced: (Tam 10 - S65°E - 25, Spruce 11 - N56°W - 25)
- 1892: County Survey by Wm. H. LeRoy - Set 3" sq. cedar stake & referenced.
- 1910: County Survey by Jos. W. McNeil - $\frac{1}{2}$ stake in road bed.
- 1976: County Road Plan - $\frac{1}{2}$ " iron and referenced.
- 1976: Survey by David B. Guthrie - Exis. nail and referenced.
- 1982: Survey by Duane MacNeill - Found Mon. Box.
- 1984 & 1992: Surveys by Earl T. Lewis - Found Mon. Box and referenced.
- 1988: Survey by David B. Guthrie - Found iron stake in Mon. Box.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found $\frac{1}{2}$ " iron rod in Monument Box and three existing witnesses as per 1992 Survey by Earl T. Lewis and one witness (S85°E - 95.88' - N.W. Cor. Hse.) as per 1976 County Road Plan and 1976 Survey by David B. Guthrie. This corner position is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set 3" dia. aluminum cap, stamped to identify corner over existing $\frac{1}{2}$ " iron rod in Monument box.
 Existing witnesses are:
 Fe. Post - N85°E - 53.65'
 P. Pole - S20°E - 116.63'
 Pipe - West - 50.00'
 N.W. Bldg. Cor. - S85°E - 95.90'

P.A. 345 ALPENA COUNTY
 PEER APPROVED Oct. 27 1994
D.B. Lutz

Signed by Thomas L. Fabis Date Dec. 5, 1994
 Surveyor's Michigan License No. 315911

