

SURVEY &
 REMONUMENTATION
 COMMISSION
 APR 08 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Dec 8 10 11 AM '94
Maureen A. Johnston
 REGISTER OF DEEDS

For corners in Alpena (County)

Located In: Corner Code #

1. Public Land Survey	T <u>29N</u> R <u>7E</u>	G-12(W $\frac{1}{2}$, 34)
	T _____ R _____	Ossineke Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas L. Fabis, in a field survey on May 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1839: G.L.O. Survey by Lewis Clason - Set post & referenced: (Cedar 7 - S62°E - 7, Aspen 16 - N68°W - 20).
 - 1914: County Survey by Jos. W. McNeil - set large cedar stake in road bed.
 - 1976: County Road Plans - 1/2" iron and referenced.
 - 1979, 1982 and 1988: Surveys by Duane MacNeill - Found 1/2" re-rod in Mon. Box and referenced.
 - 1987 and 1993: Surveys by Earl. T. Lewis - Found Mon. Box and referenced.
 - 1992: Survey by David B. Guthrie - Found 1/2" iron rod in Mon. Box & referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" iron rod in Monument Box and four existing witnesses. This corner position is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set 3" dia. aluminum cap, stamped to identify corner, over existing 1/2" iron rod in monument box.

Existing witnesses are:
 Tele. Pole - 66.08' - S35°W.
 Conc. Mon. - 50.08' - West
 Exist Tag #22435 in 5" W. Pine - 55.18' - N50°W
 Exist Tag #22435 in 40" W. Pine - 125.34' - S20°W

P.A. 345 ALPENA COUNTY
 PEER APPROVED Oct. 27, 1994
Pat B. Luce

Signed by Thomas L. Fabis
 Surveyor's Michigan License No. 31591



Date Dec. 5, 1994