

NOV 16 1998

P.A. 345 ALPENA COUNTY
PEER APPROVED *S. J. / S. J.*
Dot B. [Signature]

1998 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE SECTION
Filing Requirement of Act 74, Mich. P.A. 1970 Liber 000002 Page 0147

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>7E</u>	<u>H-7</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
County of Alpena
Recorded
08-20-1998 09:18:42
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on February 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7								●					
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO Survey by Lewis Clason-set 1/4 section post; referenced: Hemlock 15-N38W-18/Cedar 22-S27E-13
- 1904: County Survey by Jos. W. McNeil-O.B.T. down and stub of another/Set new cedar stake 4" square; referenced: Cedar 22-S27E-13/Hem. 15-N38W-18
- 1965: Road plans by James L. Scott-found PK Nail; referenced: 6" Elm-N30E-61.10'/12" Spruce-N30W-61.00'/12" Spruce-S10W-54.10'
- 1973: Survey by Richard L. Miller-found 1/2" rod; referenced: 6" Elm-N30E-61.10'/12" Spruce-N30W-61.00'/12" Spruce-S10W-54.10'
- 1973: Recorded Corner by Richard L. Miller-found 1/2" rod; referenced: 6" Elm-N30E-61.10'/12" Spruce-N30W-61.00' 12" Spruce-S10W-54.10'
- 1983: Survey by Earl T. Lewis-existing iron; referenced: 14" Spruce-S10W-55.2'/Tel. Pole-N60W-117.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: Remon Survey by Daniel T. Kibbe-found 1/2" rebar centerline of E-W road
This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod in monument box.
Referenced:
Nail in 16" Spruce S14W-54.8'
Wooden guardrail post-N80E-63.32'
Wooden guardrail post-S57E-43.13'
End wooden guardrail post-S80W-75.41'
P.Pole-N60W-117.48'



Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278

Date August 14, 1998