

**SURVEY & REMONUMENTATION**

**OCT 19 1999**

1998 ALPENA COUNTY REMONUMENTATION CORNER

Liber **000002** Page **0180**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>29</u> N R <u>7 E</u>	H-11	
	T ___ R ___	Ossineke Twp.	
	T ___ R ___		
	T ___ R ___		
2. Property Controlling in Section	S ___ T ___ R ___		
	S ___ T ___ R ___		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		

STATE OF MICHIGAN  
County of Alpena  
Recorded  
12-22-1998 12:43:53  
Kathy J. Mataash  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas L. Fabis, in a field survey on Dec. 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11								●					
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
 1839: G.L.O. Survey Lewis Clason Set Sec. post & referenced: Cedar 12 N49W 12, Do 8 S39E 18.  
 1909: County Survey Jos. McNeil Set 1/4 S. 27 and 34 in road bed.  
 1974: Survey W.O. 4-4974 James Scott Found R.R. and referenced.  
 NO DATE: Rd. Comm. Surv. Notes Gary St. Charles Ex. 1/2" Rerod & referenced.  
 1982: Survey L.2 P.278 D.R.MacNeill Fd. 1/2" Rerod & referenced.  
 1995: Survey W.O. 4-2414-S Earl Lewis Ex. 1/2" Rerod & referenced.  
 1997: Survey Notes Wilcox/Hendricks Rebar Fence to N. & S.

P.A. 345 ALPENA COUNTY  
PEER APPROVED 12/17/98  
*[Signature]*


- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1998: Found 1/2" iron rod 4 feet South of centerline of Scott Rd. (gravel surface), on line with old N-S fence to the North. Also, found 2 existing witnesses: shiner in Fe. Cor. Post - North - 38.52' and Lewis tag in P. Pole - N6E - 38.21'.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1998: Set 3" dia. aluminum cap, stamped to identify the corner, over the existing 1/2" iron rod. Witnesses are:  
 Exis. shiner in Fence Post North 38.52'  
 Exis. Lewis Tag in P. pole N6E 38.21'  
 Set Tag #31591 in 8" Cedar S60W 71.79'  
 Set Tag #31591 in 7" Spruce S20W 22.59'  
 Set Tag #31591 in Fe. Post N20W 41.11'

Signed by Thomas L. Fabis  
Surveyor's Michigan License No. 31591



Date December 21, 1998