

NOV 16 1998

P.A. 345 ALPENA COUNTY
PEER APPROVED 8/10/98
D. T. Kibbe

1998 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Liber 00002 Page 0148

For corners in

<u>Alpena</u> (County)	Located in:	Corner Code #/
1. Public Land Survey	T <u>29N</u> R <u>7E</u>	<u>1-7</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
County of Alpena
Recorded
08-20-1998 09:18:49
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on February 24, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7								●				
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO Survey by Lewis Clason-set post corner section; referenced: Spruce 10-S43E-10 links/Aspen 11-N70W-19 links
- 1904: County Survey by Jos W. McNeil-Ran to corner
- 1965: Road plans by James L. Scott-found 18" T iron: referenced: P.Pole-N30E-48.35'/Corner fence post-N10W-56.60'/Corner fence post-South-32.30'
- 1973: Survey by Richard L. Miller-found 5/8" rod: referenced: P.Pole-N30E-48.35'/Fence Corner-N10W-56.60' Fence Corner-South-32.30'
- 1973: Recorded Corner by Richard L. Miller-found 5/8" rod: referenced: P.Pole-N30E-48.35'/Fence Corner-N10W-56.60' Fence Corner-South-32.30'
- 1977: Survey by David B. Guthrie-existing 3/4" iron rod: referenced: P.Pole-S10E-45.23'/Fence Post-N5W-58.23' Fence Post-N45E-73.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: Remon Survey by Daniel T. Kibbe-found 5/8" rebar centerline of E-W road and centerline trail to north. 9' E. of fence line to the N & 36' West of a fence line to the north.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod in monument box.

- Referenced:
- Found nail set tag above in P.Pole-S04W-45.28'
 - Set tag in fence post over nail-N45E-75.08'
 - Chisel mark east side of West gate post-North-59.29'
 - Set tag in 5" Cedar-S06W-94.18'

Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278



Date August 14, 1998