

**2000 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alpena</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 29N R7E	K-1
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	



L- 2 P- 318
08/16/2000 09:32A
Page: 1 of 1

Kathy J. Natash, Register Alpena Co., MI LDC 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel T. Kibbe, in a field survey on March 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO Survey by Lewis Clawson Intersected N. Boundary 59 links East of post. Referenced: Cedar 9-S40°E-28 Cedar 6-S45°W-03
- 1904: County Survey by Jos. W. McNeil From Sec corner 1 and 2 on town line stake for 29-7 set on east side of ditch 59 links east of stake 35 and 36.
- 1996: Survey by Earl T. Lewis Existing 1/2" rerod Referenced:
Power Pole-S80°E-241.45'
Power Pole-S45°E-50.01'
Fence Post-S50°W-46.33'
Power Pole-N10°E-236.01'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar .6' deep. 3.5' South of E & W road and 2' West of N & S road. At K-13 T30N R7E found axle shaft 19.76' West of above 1/2" rebar. At true position of K-1 T29NR7E found 1" axle shaft 1.5' deep 38.83' East of K-13 and 19.07' East of above referenced 1/2" rebar.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2000: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod 6" below grade. Referenced:
Found axle shaft at K-13 West 38.83'
Found 1/2" rebar West 19.07'
Found tag #27452 in power pole S39°E 35.58'
Found tag #27452 in fence post S61°W 62.04'
Found tag #27452 in power pole N07°E 233.81'

P.A. 345 ALPENA COUNTY
PEER APPROVED 7-12-2000
D.J.B.

Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278



Date August 14, 2000

PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

FORM APPROVED BY MICHIGAN STATE BOARD OF

REVISED JAN., 1983
REVISED OCT., 1995

**SURVEY &
REMONUMENTATION**

JAN 25 2001

SECTION