

1994 ALPENA COUNTY REMONUMENTATION CORNER
 SURVEY & REMONUMENTATION
 APR 06 1995
 COMMISSION

RECORDED
 ALPENA COUNTY MI
 007219

1 PAGE 332

DEC 12 9 31 AM '94
 REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alpena (County) Located In: 29N 7E Corner Code # L-7

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Earl T. Lewis in a field survey on July 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (GLO) August 11, 1839, Lewis Glason, Marked Soft Maple 8 in diam for corner, no witnesses given.
 1915, Joseph W. McNeil set corner, no monumentation or witnesses given.
 1992, D.R. MacNeill, P.S., no monumentation or witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 11"X5/8" rebar in centerline of road.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1994, Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" X 18" rebar in monument box, witnessed:
 N 75° W 103.75' Power Pole
 N 15° E 78.00' 6" Oak
 N 20° W 73.39' 1" Apple
 South 38.10' Steel Gate Post

P.A. 345 ALPENA COUNTY
 PEER APPROVED 9/29/94
D. R. MacNeill

Signed by Earl T. Lewis Date December 6, 1994
 Surveyor's Michigan License No. 27452