

**SURVEY & REMONUMENTATION**

**OCT 19 1999**

Liber **00002** Page **0185**

**1998 Alpena County Remonumentation Corner LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>7E</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 County of Alpena  
 Recorded  
 01-04-1999 09:12:32  
 Kathie J. Matson  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel T. Kibbe, in a field survey on October 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1939: GLO Survey by Lewis Clason-Set 1/4 post, Refernced: Y.Pine 22-S75W-39, Y.Pine 14-N68E-58
- 1913: County Survey by Jos. W. McNeil-Set 1/4 Section 25 & 36, and made NWT. No old marks found. Refernced: W.Pine Stump 18-N30E-51 1/2,
- 1972: Subdivision Plat by James L. Scott-Refernced corner for Green Oaks Sub. recorded in Liber 5, Pgs 22 & 23 of Plats.
- 1978: Survey by David B. Guthrie-Existing 1/2" iron
- 1985: Survey by Earl T. Lewis- Existing 1/2" rod. Refernced: P.Pole-S15W-49.05'
- 1986: Survey by Earl T. Lewis- Existing 1/2" rod. Refernced: P.Pole-S15W-49.05'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1998: Remon Survey by Daniel T. Kibbe-Found bar & cap (identity unknown) CL Scott Road E-W on a fence line to the North and on the East edge of 12' gravel drive (Sawmill Drive) to South, Concrete monument and cap 27452 is 33' North.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1998: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.  
 Refernced:  
 Found tag and set tag in P.Pole-S25W-48.99'  
 Set tag in 10" Poplar-N32W-42.85'  
 Found concrete monument-N05E-32.70'  
 Set tag in 8" R.Pine-N66E-76.72'  
 Set tag in 10" R.Pine-S33E-87.40'

P.A. 345 ALPENA COUNTY  
 PEER APPROVED 12/17/98  
*D. T. Kibbe*



Signed by *Daniel T. Kibbe*  
 Surveyor's Michigan License No. 37278

Date December 17, 1998