

**SURVEY &  
REMONUMENTATION**

**OCT 19 1999**

Liber **00002** Page **0186**

**SECTION**

**1998 Alpena County Remonumentation Corner  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
County of Alpena  
Recorded  
01-04-1999 09:12:43  
Kathy J. Matask  
REGISTER OF DEEDS

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>7E</u>	<u>M-9</u> ✓
	T <u>29N</u> R <u>8E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel T. Kibbe, in a field survey on October 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1939: GLO Survey by Lewis Clason-Set post at corner 24 & 25, Referenced: Y.Pine 20-N22 1/2W-50, Y.Pine 15-S49W-18
- 1905: County Survey by Jos. W. McNeil-Found old stake standing and remains of one OBT. Referenced: Y.Pine 18-S49W-18 OBT and roots of other. Set new stake green B. Oak 4" square. No NWT
- 1906: County Survey by Jos. W. McNeil-Corner previously established by him. Set new cedar stake.
- 1912: County Survey by Jos. W. McNeil-Corner previously established by him from OBT's.
- 1973: Survey by James L. Scott- Found 1/2" iron rod. Referenced: P.Pole-N45W-46.84', 12" Maple-S45W-54.83'
- 1983: Survey by Duane R. MacNeill-Found 1/2" rerod. Referenced: 12" red oak-S40W-55.22', P.Pole-N45W-47.33', 10" red oak-N38E-50.60' Recorded Liber 2, Pg 245.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1998: Remon Survey by Daniel T. Kibbe-Found concrete monument in the CL of Lytle Road N-S, 2' North of CL Kitter Road E-w. Found at the ROW 27452 bar & cap 33' West and 33' North.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1998: Placed 3" Alpena County cap stamped to identify the corner over the 1/2" iron rod in the concrete monument. Referenced:  
 Found tag in P.Pole-N40W-47.20'  
 Found nail & flag, set tag in P.Pole-N40W-47.70'  
 Found nail & flag, set tag in 10" R. Oak-N50E-50.45'  
 Found nail & flag, set tag in 18" R. Oak-S53E-54.84'  
 Found nail & flag, set tag in 10" Poplar-S69W-62.45'  
 Found bar & cap-N40W-46.10'

P.A. 345 ALPENA COUNTY  
PEER APPROVED 12/17/98  
*D.T. Kibbe*



Signed by *Daniel T. Kibbe*  
Surveyor's Michigan License No. 37278

Date December 17, 1998