

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DEC 12 9 31 AM '94

REGISTER OF DEEDS

REMONUMENTATION COMMISSION APR 06 1995

Table with columns: Located In, Corner Code #, Public Land Survey, Property Controlling in Section, Miscellaneous, Property in Sec.

Register of Deeds Stamp & File Number

Lot No. Recorded Plat Private Claims

Earl T. Lewis July 22 19 94

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration: (GLO) July 28, 1839, Lewis Glason set post, no monumentation given, witnesses given: Tam. 10, N 24 W, 16 / Tam. 12, S 61 E, 25 1894, Fred A. Rice, no monumentation or witnesses given. 1976, David B. Guthrie, found 1/2" rod, witnesses given: North 47.34' Power Pole / N 80° W 178.4' Power Pole 1979, D.R. MacNeill, P.S., found 1/2" re-rod, no witnesses given.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar raised with 1/2" rebar.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994, Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" X 24" rebar in monument box, witnessed: North 48.30' Power Pole N 75° W 176.70' Power Pole N 75° W 166.00' Rd. Sign S 45° W 192.30' Power Pole N 15° E 40.40' Balm of Gilead

P.A. 345 ALPENA COUNTY PEER APPROVED 9/29/94

Signed by Earl T. Lewis Date December 6, 1994 Surveyor's Michigan License No. 27452