

MAY 18 1997

1996 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 29N R 8E C-8
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
County of Alpena
Recorded
10-17-1996 11:46:0
Kathy J. Matash
REGISTER OF DEEDS

Liber 00002 Page 0060

Register of Deeds Stamp & File Number

I, Daniel T. Kibbe in a field survey on July 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
- 1839: GLO Survey by Lewis Clason - set post & referenced: Cedar 10 - N 29 W - 33, W. Pine 16 - S 34 E - 28.
 - 1905: County Survey by Jos. W. McNeil - in road bed.
 - 1910: County Survey by Jos. W. McNeil - in road bed.
 - 1960±: Spruce Rd. plans on file at Alpena County Road Commission.
 - 1972: Survey by Larry Beauregard - existing monument.
 - 1982: Survey by Duane MacNeill - found 1/2" rerod.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1996: Found 5/8" rebar located 1' W. of C/L Spruce Rd. and on fence line to W. and field line to E.

This corner position is compatible with county and local surveys.
This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 7/18/96


D.T. Kibbe

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod in monument box.

Referenced:

- N 87° E - 76.75' - Set N/Tag in 10" Scotch Pine
- N 20° E - 127.50' - Set N/Tag in Power Pole
- N 53° E - 128.05' - NW corner brick front house
- N 80° W - 50.40' - Set N/Tag in fence post



Signed by *Daniel T. Kibbe*

Date October 15, 1996

Surveyor's Michigan License No. 37278