

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 12 9 31 AM '94

Myra D. Johnston
REGISTER OF DEEDS

1994 ALPENA COUNTY
REMONUMENTATION
APR 06 1995
COMMISSION

For corners in
Alpena
County

Located In: Corner Code #

29N 8E

D-7

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Earl T. Lewis July 22 19 94

I, Earl T. Lewis, in a field survey on July 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (GLO) July 17, 1839, Lewis Glason set post, no monumentation given, witness given: Hem 10, N 52 1/2 E, 22 / Red Maple 16, S 46 W, 26.
- 1892, Fred A. Rice, set stake, no witnesses given.
- 1905, Joseph W. McNeil, found corner set by Rice, no witnesses given.
- 1972, Edward LaCross, P.S., found iron, no witnesses given.
- 1985, D.R. MacNeill, P.S., no monumentation or witnesses given.
- 1992, D.R. MacNeill, P.S., found 1/2" re-rod, no witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar raised with 1/2" rebar.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994, Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" X 24" rebar in monument box, witnessed:
South 53.15' Telephone Marker
S 45° W 81.75' 12" Apple
N 45° W 80.85' Power Pole
South 107.60' 35" Elm

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/29/94
W.D. C. C. C.

Signed by Earl T. Lewis Date December 6, 1994

Surveyor's Michigan License No. 27452