

MAY 1 8 1997

COMMISSION

1996 Alpena County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Alpena (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

STATE OF MICHIGAN
County of Alpena
Recorded
10-17-1996 11:47:
Kathy J. Matash
REGISTER OF DEEDS

Liber 00002 Page 0066

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and a small circle in row 13, column C.

I, Daniel T. Kibbe in a field survey on September 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO Survey by Lewis Clason - referenced: Hemlock 12 - N 20 E - 16 / Cedar 6 - N 49 W - 20.
1889: County Survey by Fred A. Rice - witness trees not found.
1976: Survey by Dave Guthrie - set nail.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: No monumentation found. Corner position established by proportionate methods in accordance with county surveys. Corner position established in centerline of E-W road bed on fence line to North.

This corner position is compatible with county surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 7/14/96

Handwritten signature: Del B. Turner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod 6" below grade.

- Referenced:
N 15° W - 32.06' - Set N/Tag in 10" Elm
N 40° W - 46.20' - Set N/Tag in 16" Poplar
S 35° W - 39.55' - Set N/Tag in E. gate post
South - 35.51' - Set N/Tag in 8" Poplar



Signed by Daniel T. Kibbe

Date October 15, 1996

Surveyor's Michigan License No. 37278