

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DEC 12 9 31 AM '94

REGISTER OF DEEDS

1994 ALPENA COUNTY REMONUMENTATION COMMISSION APR 06 1995

Table with columns: Located In: (Town, Range, Section), Corner Code #. Row 1: 29N 8E E-7

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 7, column D.

Earl T. Lewis July 22 19 94

I, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (GLO) July 14, 1839, Lewis Glason set post, no monumentation given, witness given: Beech 10, S 59 E, 10 / Do 12, N 52 W, 62
1886, William Mirre, set 4X4 cedar stake with pieces of iron from an old stove in the bottom of the hole, no witnesses given.
1892, Fred A. Rice, no witnesses given.
1984, D.R. MacNeill, P.S., no monumentation or witnesses given.
1985, D.R. MacNeill, P.S., no monumentation or witnesses given.
1992, D.R. MacNeill, P.S., found PK nail over iron, no witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar raised with 1/2" rebar raised with PK nail.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994, Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" X 24" rebar in monument box, witnessed:
S 45° W 57.40' 18" Spruce (found Fabis tag)
S 50° W 53.00' Telephone Pole
N 45° W 59.60' Telephone Pole (found tag)
N 45° E 62.80' Telephone Riser
N 50° W 80.72' 14" Red Pine (found Fabis tag)

P.A. 345 ALPENA COUNTY PEER APPROVED 9/29/94

Signed by Earl T. Lewis Date December 6, 1994
Surveyor's Michigan License No. 27452