

JAN 21 2000

1999 ALPENA COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena
(County)

Located In:

Corner Code #



L- 2 P- 239
11/22/1999 01:43P
Page: 1 of 1
Kathy J. Matash, Register Alpena Co., MI LDC 9.00

- 1. Public Land Survey T29N R8E E-8
 T___ R___ Sanborn Twp.
 T___ R___ _____
 T___ R___ _____
- 2. Property Controlling S___ T___ R___
 in Section S___ T___ R___
- 3. Miscellaneous S___ T___ R___
 Property in Sec. S___ T___ R___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas L. Fabis, in a field survey on July 27 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: G.L.O. Survey Lewis Clason Set post & referenced: Beech 12 N62½W 34, Do 14. S24E 07
- 1892: County Survey Joseph McNeil found witness trees but not according to Field Notes.
- 1905: County Survey Jos. W. McNeil Set new cedar stake flush with roadbed.
- 1998: Survey for Angela Aube by John Oliver Found 3" Pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Found 3" Pipe 2.5' East of N-S Rd. (Carriveau Rd.) centerline.
No existing witnesses.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Replaced existing pipe with 1/2" iron rod with 3" dia. alum. cap stamped to identify the corner. Set tag P.S. #31591 in the following reestablished witnesses:
Fe. Post N56W 43.54
Apple Tree S40E 39.40
Cor. Fe. Post N85E 36.57
Cor. Fe. Post N88W 36.21

P.A. 345 ALPENA COUNTY
PEER APPROVED 8/26/99
D.P.H. [Signature]

Signed by

Thomas L. Fabis

Date November 19, 1999

Surveyor's Michigan License No. 31591

