

JAN 21 2000

1999 ALPENA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Alpena
(County)

Located In:

Corner Code #



L-2 P-238
11/22/1999 01:43P
Page: 1 of 1
MI LDC 9.00

Kathy J. Mataah, Register Alpena Co., MI

1. Public Land Survey

T29N R8E E-10
Sanborn Twp.

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas L. Fabis, in a field survey on July 27 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1839: G.L.O. Survey Lewis Clason set post & referenced: Y. Birch 15 S53 1/2 W 55, Hem. 10 N65 1/2 E 18.
1905: County Survey Jos. W. McNeil found an old stake standing and both O.B.T.'s down but plainly identified, set large cedar stake.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999: Found no existing monumentation of corner or witnesses. Set 1/2" iron rod at intersection of E-W 1/4 line fence to the West with centerline of N-S gravel rd. (Carriveau Rd.).


The position of this corner is compatible with early county surveys and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1999: Set 1/2" iron capped with a 3" dia. alum. cap, stamped to identify the corner, in the position mentioned above. Set tag P.S. #31591 in the following reestablished witnesses:

- 6" R. Pine S62E 36.32
- 5" R. Pine S35E 59.16
- Cor. Fe. Post West 40.77
- Fe. Post S60W 47.22

P.A. 345 ALPENA COUNTY
PEER APPROVED 8/24/99
[Signature]

Signed by Thomas L. Fabis
Surveyor's Michigan License No. 31591



Date November 19, 1999