

REMONUMENTATION COMMISSION APR 06 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Dec 12 9 31 AM '94 Register of Deeds

Form with fields for 'Located In:', 'Corner Code #', and numbered sections 1-5 for survey details.

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numerical values.

Earl T. Lewis July 22 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

- (G1.0) July 14, 1839, Lewis Glason set post, no monumentation given, witness given: Beech 12, N 29 W, 18 / Hemlock 16, S 61 E, 22. 1892, Fred A. Rice, set stake, no witnesses given. 1905, Joseph W. McNeil, set cedar stake, no witnesses given. 1972, James L. Scott, P.S., found 1/2" rod, witnesses given: North 85.52' Power Pole / S 03° E 95.70' 8" Maple. 1978, D.R. MacNeill, P.S., set 1/2" re-rod, wit. given: N 40° W 91.62' P. P. / N 45° W 61.04' Fence Post / S 40° W 52.54' 4" Beech 1981, D.R. MacNeill, P.S., set 1/2" re-rod, witnesses given: Due South 42.23' 5" Beech / Due North 85.61 Power Pole. 1984, D.R. MacNeill, P.S., no monumentation or witnesses given. 1992, D.R. MacNeill, P.S., found re-rod, no witnesses given.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar raised with 1/2" rebar with cap, unable to identify number on cap.

P.A. 345 ALPENA COUNTY PEER APPROVED 9/29/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994, Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" X 24" rebar in monument box, witnessed: North 42.50' Fence Post (found tag) North 85.69' Power Pole (found tag) South 33.75' Telephone Marker South 50.90' 10" Maple S 70° W 81.59' Wood Fence Post



Signed by Earl T. Lewis Date December 6, 1994 Surveyor's Michigan License No. 27452