

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

DEC 12 9 31 AM '94

*Springer A. Johnston*  
 REGISTER OF DEEDS

	Located In:		Corner Code #
	29N	8E	
Public Land Survey	T	R	G-7
	T	R	
	T	R	
	T	R	
Property Controlling in Section	S	T	R
	S	T	R
Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

Earl T. Lewis July 22 1994

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
  - (GLO) July 11, 1839, Lewis Glason set post, no monumentation given, witness given: Hem 24, S 74 E, 32 / Cedar 9, N 75 1/2 W, 27
  - 1892, Fred A. Rice, set stake, no witnesses given.
  - 1905, Joseph W. McNeill, set cedar stake, no witnesses given.
  - 1972, James L. Scott, P.S., found 1/2" rod, witnesses given: N 30° E 90.63' Power Pole / S 45° E 95.70' Tel. Pole
  - 1978, D.R. MacNeill, P.S., set 1/2" re-rod, witnesses given: N 10° E 95.66' P. P. / S 10° E 108.90' P. P. / S 60° E 91.31' P. P.
  - 1981, D.R. MacNeill, P.S., set 1/2" re-rod, wit. given: S 55° E 87.01' P. P. / S 25° E 107.54' P. P. / N 30° E 94.30' P. P.
  - 1986, D.R. MacNeill, P.S., no monumentation or witnesses given (MacNeill makes reference to other existing 1/2" rod)
  - 1993, D.R. MacNeill, P.S., no monumentation or witnesses given.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
  - Found 1/2" rebar.

ALSO; Found 1/2" rebar set by D.R. MacNeill, S 53° 46' 43" E 8.55' from remonumented corner.

P.A. 345 ALPENA COUNTY  
 PEER APPROVED 11/10/94  
*D.R. MacNeill*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
  - 1994, Place Appropriately stamped Alpena County Remonumentation Aluminum Cap on existing 1/2" X 24" rebar in monument box, witnessed:
    - S 30° E 114.20' Power Pole (found tag)
    - S 70° E 96.10' Telephone Pole
    - N 40° E 91.75' Power Pole (found tag)
    - N 55° E 51.00' Road Sign
    - S 40° W 59.98' 1" Pipe



December 6, 1994

Signed by *Earl T. Lewis* Date \_\_\_\_\_  
 Surveyor's Michigan License No. 27452