

JAN 21 2000

1999 ALPENA COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena  
(County)

Located In:

Corner Code #



L- 2 P- 233  
11/22/1999 01:43P  
Page: 1 of 1

Kathy J. Matash, Register Alpena Co., MI LDC 9.00

- 1. Public Land Survey      T 29NR 8E      G-11  
   T \_\_\_ R \_\_\_      Sanborn Twp.
- 2. Property Controlling      T \_\_\_ R \_\_\_  
in Section                    T \_\_\_ R \_\_\_
- 3. Miscellaneous            S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec.            S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas L. Fabis, in a field survey on July 27, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: G.L.O. Survey Lewis Clason set post & referenced: Elm 26 S42E 28, B. Ash 4 N35W 23.
- 1892: County Survey Joseph McNeil one wit. large Elm standing.
- 1902: County Survey Jos. W. McNeil cor. in creek bottom plain, large green elm and large cedar stake measured Easterly in road.
- 1997: Lewis & Lewis Survey W.O. 0403045S Wayne Lewis set 1/2" rerod w/cap & referenced.
- 1998: Wilcox Field Notes W.O. 98692 found red capped rerod centerline of rd.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Found 1/2" iron rod & red cap P.S. #41922 in centerline of E-W gravel Rd. (Scott Rd.). Found 2 witnesses confirming Lewis survey of 1997.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Removed existing red cap and set 3" dia. alum. cap, stamped to identify the corner over the existing 1/2" iron rod. Witnesses are:  
Center of steel guard post S20E 15.98  
Center of steel guard post N64E 30.08  
Tag #31591 in 6" Cedar N58W 92.92  
Tag #31591 in 11" Cedar N46W 86.22

P.A. 345 ALPENA COUNTY  
PEER APPROVED 8/26/99  
*D.P.B. [Signature]*

Signed by

Thomas L. Fabis

Date November 19, 1999

Surveyor's Michigan License No. 31591

