

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 29 NR 9 E
28 4E

Alpena COUNTY

DESCRIPTION OF CORNER Corner common to Sections 32 & 33 on south
boundary of T29N, R9E
DESCRIPTION OF CORNER MONUMENT 4" pipe with 4" brass cap

WITNESSES TO CORNER

8" Cedar - N72W - 27½ links
7" Cedar - N20E - 30½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found a very old square post, scribed 32 on NW face in place. Corner faced by a Cedar NBT which was marked over 30 years ago as determined by ring count. One possible original B T is down and rotted. Checks government record for stream crossing east.

Closing corner for Sections 4 & 5, T28N R9E is 29 links east.

Corner was placed and witnessed April 12, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/9/57
REGISTERED LAND SURVEYOR