

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 29 NR 9 E ..  
28 96

Alpena COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side of Section 34, T29N R9E

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" W. Ash - N16W - 7 1/2 links  
7" W. Ash - N86E - 25 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found an old square stake, scribed 1/4, in place which appeared to be of approximately the same age as the Section corner east. Checks for distance with the Section corner east and was accepted as the 1/4 corner in this survey.

1/4 corner for Section 3, T28N R9E is 36 links east.

Corner was placed and witnessed April 12, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/9/57  
REGISTERED LAND SURVEYOR