

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 NR. 9 E. 28 92

Alpena COUNTY

DESCRIPTION OF CORNER Corner common to Sections 33 & 34 on south
boundary of T29N R9E.
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" W. Birch - N53E - 40½ links
10" Maple - N34W - 83 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Corner was established by proportionate measurement between corner to Sections 32 & 33 west and 1/4 corner on south side Section 34 east. No positive evidence of original B.T.s. Corner checks with swamp edge east and west. Checks fairly good with Rice survey of 1890 with regard to D&M RR crossing east.

Closing corner for Sections 3 & 4, T28N R9E is 96 links east.

Corner was placed and witnessed April 11, 1957.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 5/9/57