

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 NR. 9 E
28 96

Alpena COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side Section 33, T29N R9E

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" B. Oak	-	S80E	-	59½ links
6" B. Oak	-	N47W	-	61½ links
18" R. Pine	-	N46E	-	56½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Corner was established by proportionate measurement between Section corners of Section 33, T29N R9E. No positive identification of the original BTs could be found. An old stake, scribed 33, was found in the vicinity but its position could not be found.

The 1/4 corner for Section 4, T28N R9E is 62½ links east.

Corner was placed and witnessed April 11, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/9/57
REGISTERED LAND SURVEYOR