

# SURVEY & REMONUMENTATION

FEB 03 1998 1997 ALPENA COUNTY REMONUMENTATION CORNER

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in

Alpena  
(County)

Located In:

Corner Code #

- |                                      |   |            |   |           |                     |
|--------------------------------------|---|------------|---|-----------|---------------------|
| 1. Public Land Survey                | T | <u>30N</u> | R | <u>5E</u> | <u>K-5 (SW, 12)</u> |
|                                      | T |            | R |           | <u>Green Twp.</u>   |
|                                      | T |            | R |           |                     |
|                                      | T |            | R |           |                     |
| 2. Property Controlling in Section   | S |            | T |           |                     |
|                                      | S |            | T |           |                     |
| 3. Miscellaneous Property in Section | S |            | T |           |                     |
|                                      | S |            | T |           |                     |

Liber **00002** Page **0085**  
 STATE OF MICHIGAN  
 County of Alpena  
 Recorded  
 08-06-1997 10:45:48  
 Kathy J. Matash  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas L. Fabis, in a field survey on May 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1840: G.L.O. Survey by Lewis Clason - Set post & referenced: (Beech 8 N45W 45, Do 8 S36E 25).
- 1929: Three County Surveys by Wm. LeRoy - Cedar stake 4" sq. & referenced.
- 1974: Survey Witness Records & L.C.R.C Liber 1 Page 49 by Delmer Porter - Found 3/4" Pipe & referenced.
- 1976: Recorded Surveys by Delmer Porter Liber 1 Page 436 & 437, Liber 2 Page 349 - Found 3/4" Pipe and referenced.
- 1994: Survey Notes by Farrier Surveying - Found 1 1/2" Iron Pipe, Fits L.C.R.C. Wit's. for 3/4" Pipe.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1997: Found 1 1/2" Iron Pipe pinched and bent. Also found 2 witnesses as per Porter's L.C.R.C. and recorded surveys mentioned above.


The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY  
 PEER APPROVED 4/19/97

*D. B. [Signature]*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1997: Removed existing bent Iron Pipe and replaced it with a 1/2" iron rod with a 3" dia. aluminum cap stamped to identify the corner.  
 Set tags P.S. #31591 in the following witness objects:  
 Anchor Pole - N15E - 43.10'  
 8" Ash - N55W - 55.53'  
 24" Oak - S38W - 83.17'  
 6" W. Birch - S20E - 55.45'



Signed by Thomas L. Fabis

Date July 31, 1997

Surveyor's Michigan License No. 31591