

SURVEY & REMONUMENTATION

JUL 30 1999

1997 ALPENA COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>5E</u>	<u>L-9 (S$\frac{1}{2}$, 24)</u> <u>Green Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 00002 Page 0073

STATE OF MICHIGAN
County of Alpena
Recorded
08-06-1997 10:43:40
Kathe J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas L. Fabis, in a field survey on May 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey by Lewis Clason - Set post & referenced: (Beech 10 S56E 54, Do 12 N56W 40).
- 1888 & 1893: County Surveys by Fred A. Rice - Visited corner.
- 1993: Survey Notes by Dan Kibbe of Wilcox Associates - Set Bar & cap prorated against 1888 Rice Survey. Falls on fence line North.
- 1995: Survey W.O. 4-2517-M by Earl T. Lewis - Found 1/2" rered w/cap and referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found 1/2" iron w/yellow cap and the following witnesses: (4" Ash - North - 26.30', P. Pole - S45E - 88.70', and 30" Maple - S58W - 57.9') which match the references by Earl T. Lewis in the 1995 Survey.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 6/19/97
Ed B. Carr

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Set 3" dia. aluminum cap, stamped to identify the corner, over the existing 1/2" iron rod.

Reestablished witnesses are:

- Tag #27452 in 4" Ash - North - 26.30'
- Unknown tag in P. Pole - S45E - 88.70'
- Unknown tag in 30" Maple - S58W - 57.9'
- Set tag #31591 in 7" Apple-S13W - 32.30'



Signed by Thomas L. Fabis

Date July 31, 1997

Surveyor's Michigan License No. 31591