

SURVEY & REMONUMENTATION

FEB 03 1998

1997 ALPENA COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Liber **00002** Page **0075**

For corners in	<u>Alpena</u>	Located In:	Corner Code #
	(County)		
1. Public Land Survey	T <u>30N</u> R <u>6E</u>	<u>B-9, (S$\frac{1}{2}$, 19)</u>	<u>Green Twp.</u>
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN
County of Alpena
Recorded
08-06-1997 10:44:02
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9	●												
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Thomas L. Fabis, in a field survey on May 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey by Lewis Clason - Set post & referenced: Beech 10 N65W 45, Do 10 S31E 42
- 1907: County survey by Jos. McNeil - Set cedar stake 4" square & witnessed.
- 1973: Survey Liber 1 Page 195 by James Scott - Used corner.
- 1974: Survey R.S.Scott Eng. W.O. 4-4943 by Robert Scott and Field Notes by David Guthrie- Existing 1/2" Iron.
- 1970's: Alpena County Rd. Comm. Survey Records by Gary St. Charles - 1/2" Iron & referenced.
- 1978: Survey R.S.Scott Assoc. W.O. 4-5655 by David Guthrie - Exis. 1" Iron & referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- 1997: Found 1/2" iron and one existing witness (old shiner in Power Pole stump - S5E - 33.5').

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 6/19/97
Del B. C...

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Set 3" dia. aluminum cap, stamped to identify the corner over the existing 1/2" iron rod.
- Reestablished witnesses are:
 - Set tag #31591 in 8" Maple - N50E - 95.88'
 - Set tag #31591 in P. Pole - N8W - 33.64'
 - Set tag #31591 in P. Pole - S2W - 33.08'
 - Steel Gate Post - S30E - 80.35'



Signed by Thomas L. Fabis

Date July 31, 1997

Surveyor's Michigan License No. 31591