


**1999 Alpena County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 21 2000

For corners in

<u>Alpena</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>6E</u>	<u>B-13</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	 Kathy J. Matash, Register Alpena Co., MI LDC 9.00
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
	S _____ T _____ R _____	

SECTION

L-2 P-286
12/10/1999 01:39P
Page: 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on June 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: GLO Survey by Lewis Clason: Set qu. Sec. Post: Referenced: Y. Pine 22-N25E-45/W.Pine 6-N31W-09
- 1889: County Survey by Wm H. LeRoy: From 1/4 S. in South side Sec. 31, T30N, R6E, Referenced: Y. Pine Stump 22-N25E-45 original BT Note: Set 1/4 Corner for North side of Sec. 6, 70 links East.
- 1908: County Survey by Jos. W. McNeil: Intersect 74 links South of 1/4 S. on South side of Sec. 31-30-6E set by Wm. H. LeRoy from one OBT. Set new cedar stake.
- 1977: Survey by David B. Guthrie: Set 1/2" iron. Referenced: Transformer Pole-S85W-36.25/8" Balsam-N45E-44.43/18" Aspen-N70E-49.00'.
- 1977: Recorded Corner by David B. Guthrie: Set 1/2" iron rod in line with SW & SE Sec. Corners and N & S 1/4 line fence. Referenced: Transformer Pole S85W-36.25/8" Balsam-N45E-44.43/18" Aspen-N70E-49.00'.
- 1986: Survey By David B. Guthrie: Existing 1/2" Iron Rod. Referenced: Utility Pole-S50W-69.72'/Utility Pole-S40W-36.60'/Clump of Oaks-North-57.75'.
- 1989: Survey by David B. Guthrie: Referenced corner.
- 05/96: Survey by Daniel T. Kibbe: Found 1/2" Rebar of record.
- 11/96: Survey by Daniel T. Kibbe: Found 1/2" Rebar of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999: Remon. Survey by Daniel T. Kibbe-Found 1/2" rebar 2' North of CL road, fence line North.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1999: Placed 3" Alpena County cap stamped to identify the corner over 1/2" iron rod.
Referenced:
20" Clump of oaks-set tag-N5E 57.79'
Guy Pole - found tag 22435- S35W 36.05'
Utility Pole - set tag S62 W 69.65'
Utility Pole - set tag N70 W 105.15'
Remon. corner (B1)-East-42.90

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99
D. J. B. [Signature]

Signed by *Daniel T. Kibbe*
Surveyor's Michigan License No. 37278

Date November 30, 1999

