

**SURVEY & REMONUMENTATION**

**FEB 03 1998** 1997 ALPENA COUNTY REMONUMENTATION CORNER

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

Liber **00002** Page **0088**

For corners in

Alpena  
(County)

Located in:

Corner Code #

- |                                      |   |            |   |           |                     |
|--------------------------------------|---|------------|---|-----------|---------------------|
| 1. Public Land Survey                | T | <u>30N</u> | R | <u>6E</u> | <u>C-9 (SE. 19)</u> |
|                                      | T | _____      | R | _____     | <u>Green Twp.</u>   |
|                                      | T | _____      | R | _____     | _____               |
|                                      | T | _____      | R | _____     | _____               |
| 2. Property Controlling in Section   | S | _____      | T | _____     | _____               |
|                                      | S | _____      | T | _____     | _____               |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | _____               |
|                                      | S | _____      | T | _____     | _____               |

STATE OF MICHIGAN  
County of Alpena  
Recorded  
08-06-1997 10:46:25  
Kathy J. Matash  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas L. Fabis, in a field survey on May 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1840: G.L.O. Survey Lewis Clason-Set post & referenced: (HD Maple 18 S50W 48, Beech 10 N56E 20).
- 1906: County Survey Wm. LeRoy - Gas pipe 1 1/2 x 24"
- 1907: County Survey Jos. McNeill - gas pipe in road bed for cor.
- 1959: M.S.H.D. Survey Corner Records - Set 3/4" Bar after construction & referenced.
- 1974: Survey W.O. 4-4943 Robert Scott & Notes David Guthrie - Exis. 1" Iron Bar.
- 1978: Survey W.O. 4-5655 David Guthrie - Exis. 1" Iron & referenced.
- 1970's: County Rd. Comm. Records Gary St. Charles - 1/2" Iron & referenced.
- 1984: Survey Liber 2 Page 234 Duane MacNeill - Found 1" Iron Pin.
- 1993: L.C.R.C. Liber 1 Page 295 Clifford Lindgren - 3/4" Iron Pin & referenced.
- 1995: Survey Liber 2 Page 200 Earl Lewis - Exis. 1/2" Rerod and referenced.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1997: Found 1" Iron Pin and the following witnesses: (P. Pole - N50E - 73.35', Anchor Pole - N10E - 44.60', P. Pole - S72W - 149.8', Leaning Rd. Sign - N70W - 78').

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY  
PEER APPROVED 6/19/97  
*D. B. Tom*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1997: Removed existing 1" Iron Pin and set 1/2" iron rod with 3" dia. aluminum cap stamped to identify the corner.

Witnesses are:

- Exis. MDOT tag in P. Pole - N50E - 73.35'
- Exis MDOT tag in Anchor Pole - N10E - 44.60'
- Exis MDOT tag in P. Pole - S72W - 149.80'
- Set tag P.S. #31591 in 6" Spruce - S85E - 41.64'



Signed by Thomas L. Fabis

Date July 31, 1997

Surveyor's Michigan License No. 31591