

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alpena (County)

Located In: Corner Code #

Table with 4 columns: Description, S, T, R, Corner Code. Row 1: Public Land Survey, T 30N R 07E, A1, T 30N R 06E, HI.

JUN 17 10 58 AM '96 Kathy G. Natash REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.

1. Earl T. Lewis in a field survey on April 10 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: W. Birch 12 S 31° W 15, Hem 20 S 60° W 35
1885: W. Mirre Set 3" square cedar stake with a piece of saw, a piece of stove, small stones and crockey.
1904: J. McNeil Set cedar stake. No witnesses given.
1910: J. McNeil Used corner. No witnesses given.
1990: Earl T. Lewis, P.S. Used corner. Found 1/2" rerod. Witnesses given: S 05° W 48.20' Telephone Pole, S 20° W 59.00' Power Pole Post, N 49° W 37.37' Power Pole.
Unknown: Alpena Co. Road Comm. Used corner. Found 1/2" rerod. Witnesses given: N W 66.85' Cor. Fence Post, S W 60.00' Power Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rerod with cap #22435.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/96

Earl T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Replaced 1/2" rerod with 1/2" x 24" rerod and placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on new 1/2" rerod in monument box.

- Witnesses given:
S 05° W 48.05' Power Pole
S 30° W 60.04' Power Pole
S 70° W 102.75' 10" Ash
N 40° W 45.15' 7" Spruce



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452