

RECORDED ALPENA COUNTY MI.

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alpena (County)

Located In: Corner Code #

- 1. Public Land Survey T 30N R 07E A2 T 30N R 06E N2 T R T R S T R S T R S T R

JUN 17 10 58 AM '96

Kathryn Matash REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat 5. Private Claims

Grid table with columns A-M and rows 1-13 containing numbers 1-36.

I, Earl T. Lewis, in a field survey on April 10, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Cedar 14 S 34' W 14, Cedar 16 N 48' W 35
1885: W. Mirre Used corner. Set 3" sq. cedar stake w/a piece of pan, a piece of stove, & crockery. No wit. given.
1903: J. McNeil Set cedar stake in center of road. No witnesses given.
1910: J. McNeil Used corner. No witnesses given.
1977: David B. Guthrie Used corner. Found 1/2" iron. Witnesses given: West 47.47' Power Pole, S 85° E 63.80' Power Pole, S 40° W 141.50' 15" Apple
1990: E.T. Lewis, P.S. Used corner. Pd 1/2" rod. Wit. given: N80°W 50.00' P. Pole, East 63.00' P. Pole, S25°E 132.50' P. Pole
Unknown: Alpena Rd Comm. Used corner. Found 1/2" iron. Witnesses given: West 47.47' P. Pole, S 85° E 63.80' P. Pole, S 40° W 141.50' 15" Apple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rerod in centerline of road.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/96 O.T.B. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rerod in monument box.

- Witnesses given: East 63.00' Power Pole N 75° E 36.06' 8" Apple N 80° W 49.98' Power Pole S 15° E 132.45' Power Pole



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452