

003327 RECORDED ALPENA COUNTY MI.

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy McIntosh REGISTER OF DEEDS

For corners in Alpena

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 30N R 07E A3 T 30N R 06E H3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

Earl T. Lewis in a field survey on April 10 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Cedar 22 S 41 W 31, Cedar 16 N 40 W 14
1885: W. Mirre Set 4"x3" cedar stake w/cans, a piece of iron, some crockery & a piece of a lamp.
1977: D.B. Guthrie Found 1/2" iron. Wit. given: N45 E 44.97' Power Pole, S45 W 45.45' Fe. Post, N50 W 58.65' Fe. Post
1980 & 85: E.T. Lewis Found 1/2" rod. Wit. given: S50 W 58.25' Power Pole, N50 W 58.65' Fence Post
1985: Ed LaCross Used corner. No monumentation or witnesses given.
1990: E.T. Lewis, P.S. Used corner. Found 1/2" rod. Wit. given: S 45 W 52.25' Power Pole, N 45 W 58.90' Fence Post
1992: D.B. Guthrie Found 1/2" rod. Wit given: N66 E 59.98' Cble Mrkr, N55 W 59.00' Fe. P., S83 W 48.70' Stop Sign, S75 W 58.44' U.P.
1995: G. St. Charles Recorded corner in Liber 2 of Corners, pg. 13. Found 1/2" rebar. Witnesses given: N45 E 59.44' Corner Tele. Pedestal, N50 W 59.20' Tag on Fence Post, S50 W 58.53' Tag on Power Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rered in centerline of road.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/96

Earl T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rered in monument box.

Witnesses given:

- S 55 W 58.50' Power Pole
N 60 W 63.65' Fence Post
S 45 E 89.10' 6" Cedar
S 60 E 78.90' 6" Cedar



Signed by Earl T. Lewis Date June 12, 1996
Surveyor's Michigan License No. 27452