

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 59 AM '96

Kathy J. McDosh
REGISTER OF DEEDS

For corners in
Alpena (County)

Located In:

Corner Code #

Table with 3 columns: Description, Located In, Corner Code. Row 1: Public Land Survey, T 30N R 07E, A5. Row 2: Property Controlling in Section, S T R.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.

Earl T. Lewis in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Beech 10 S 73° W 43, Beech 13 N 44° W 41
1885: W. Mirre Set 3" sq cedar stake with a horse shoe, some crockery, an axe, and small stones.
1888: Wm. Leroy Found stake set by Mirre. No witnesses given.
1901: J. McNeil Used corner. Found stake. No witnesses given.
1914: J. McNeil Set new stake in place of old one in cross roads. No witnesses given.
1992: D.B. Guthrie Fd 1/2" rod. Wit. given: N30°E 69.38' 24" Mpl, N80°E 73.00' 24" Mpl, N48°W 47.11' P.P., S24°E 106.41' 24" Mpl.
1993: E.T. Lewis, P.S. Fd 3/4" pipe. Witnesses given: N80°E 73.0' 24" Mpl, N15°E 69.4' 24" Mpl, N25°W 47.1' P.P., S75°E 49.6' S.S.
1995: G. St. Charles Recorded corner in Liber 2 of Corners, pg 13. Found 1/2" rebar. Witnesses given: N 51° W 55.25' Tag on Power Pole, N 65° E 60.50' 1/2" Rerod, S 49° E 59.50' 1/2" rerod.
Unknown: Alpena Rd Conn. Found 3/4" pipe. Wit. given: N 34° E 69.45' 29" Maple, N 84° E 73.05' 26" Maple, N 36° W 47.07' P. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" rerod w/cap #27461.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY
PEER APPROVED 5/15/96
Earl T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rerod in monument box.

Witnesses given:

- N 51° W 55.28' Power Pole
S 55° E 75.55' 12" Spruce
S 35° E 123.79' 14" Apple
N 30° E 58.15' Power Pole
N 65° E 60.06' 1/2" Rerod
S 49° E 59.42' 1/2" Rerod



Signed by Earl T. Lewis

Date June 12, 1996

Surveyor's Michigan License No. 27452