

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 17 10 58 AM '96

Kathy Matash REGISTER OF DEEDS

For corners in Alpena (County)

Located in: Corner Code #

Table with 4 columns: Item description, T/S, R, and Corner Code. Includes items like 'Public Land Survey' and 'Property Controlling in Section'.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Earl T. Lewis, in a field survey on April 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1839: Lewis Glason Set corner. Witnesses given: Maple 9 S 33° W 26, Beech 13 N 25° W 45
1885: W. Mirre Set 4" sq cedar stake with a piece of iron from a plough, some tin cans, and an axe.
1905: J. McNeil Found old stake. Set new cedar stake. No witnesses given.
1982 & 88: E. T. Lewis Found 1/2" rod. Witnesses given: N 45° E 53.47' Telephone Pole, S 45° W 65.86' Power Pole
1991: T.L. Fabis, P.S. Found 1/2" rod in mon. box. Wit. given: S30°W 58.75' P.P., S32°E 56.07' Anchor Pole, N66°E 72.59' S'ly Sign Post, N48°W 82.94' S.E. Cor. Pump Island
1995: T.L. Fabis, P.S. Found 1/2" rod in mon. box. No witnesses given.
1995: G. St. Charles Recorded cor. in Libr 2 of Cors, pg 12. Fd 1/2" rebar in mon box. Wit given: N40°E 61.18' Tag on Telephone Pole, S25°E 56.12' Tag on Anchor Pole, S40°W 58.75' Tag on Power Pole
Unknown: Alpena Rd Comm Fd 3/8" rod. Wit. given: N40°E 61.18' Tag on T. Pole, S25°E 56.12' Tag on Anchor P., S40°W 58.75' Tag on P.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996: Found 1/2" rered.

SURVEY & REMONUMENTATION

JUL 23 1996

COMMISSION

P.A. 345 ALPENA COUNTY PEER APPROVED 5/5/96

Signature of D.L. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1996: Placed appropriately stamped Alpena County Remonumentation 3" aluminum cap on existing 1/2" rered in monument box.

- Witnesses given:
N 66° E 72.25' S'ly Sign Post
N 48° W 81.70' S.E. Cor. of Pump Island
S 40° E 55.25' Anchor Pole
S 40° W 58.10' Power Pole
N 45° W 112.50' Steel Pole



Signed by Earl T. Lewis
Surveyor's Michigan License No. 27452

Date June 12, 1996