

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Alpena _____ (County)	Located In _____	Corner Code # _____	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>33</u> T <u>30N</u> R <u>6E</u> <u>4</u>		
	S <u>33</u> T <u>30N</u> R <u>6E</u> <u>11</u>		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Carl T. Kiiskila, in a field survey on December 3, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

4- This corner position was not established during the original government survey.

11- This corner position was not established during the original government survey.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

4- Established the Northwest corner of the Southeast quarter of the Northwest quarter of section 33 per B.L.M. instructions for the subdivision of a section.

11- Established the Southwest corner of the Northeast quarter of the Southwest quarter of section 33 per B.L.M. instructions for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4- Set 5/8" X 32" rered with P.S. cap #33981

Wit: 10" Red Pine	S22°E	24.93'
12" Red Pine	S88°W	25.15'
12" Red Pine	N12°W	28.16'
9" Red Pine	S80°E	19.19'
E-W Fence	North	44'
Carsonite Post	South	1'±

11- Set 1" X 32" pipe with P.S. cap #33981

Wit: 4" Balsam	S07°E	17.12'
12" Spruce	N75°W	29.03'
6" Balsam	N19°E	23.09'
4" Balsam	East	10.71'
E-W smooth wire mostly down		
Carsonite Post	North	1'±

Signed by:

Carl T. Kiiskila

Date:

10-29-02

Surveyor's Michigan License No.:

33981

